



# egistration Certificate

Carpet Name: CONSEQUENCE 2.0 - SEQUEL

MILLIKEN (AUSTRALIA) PTY LTD Licensee:

Licence Number: 008 Label Number: 14151

ACCS Contract Grading: CEHD 4\* ACCS Residential Grading: NONE Suitable for Stairs: Yes

> 14/09/2016 Date Printed:



Allow Fith Allan Firth

Secretary ACCS



CONTRACT

RESIDENTIAL

Administered by the Carpet Institute of Australia Limited ABN 11 006 829 303

PO Box 7172, St Kilda Road, Melbourne Victoria 8004 Tel: (03) 9804 5559 • Fax: (03) 9804 5560

Email: info@carpetoz.com.au • www.carpetinstitute.com.au

This certificate remains the property of the Carpet Institute of Australia Limited.

## **Carpet Details:**

# Company: MILLIKEN (AUSTRALIA) PTY LTD

Licence No: 008 Office No: 5972

N/A

/

### Names:

CONSEQUENCE 2.0 - SEQUEL

### **Details:**

Awarded Res Grade: NONE Awarded Con Grade: **CEHD** 4\* Registered On: 24/07/2014 Active: Yes Date In-Active: Manufacture Method: Tufted Twist Set: N/A Dyeing Method: Melt Dyed #Colours/Designs: 20 Backing Type: Foam Felted: N/A Spinning System: **BCF** 

# **Hexapod Scores:**

Insect Resist Agent:

Master Product:

Filament:

**Texture** Colour **Thickness** WA WA (mm) (%) 1500: 4.5 4.0 4.5 0.3 7.5 4.5 0.8 20.0 8000: 3.5 3.5 4 0 4.0

# **ACCS Test:**

Con Res Max SPM/PH Ratio: 16 16 16 Volume Density: 20 20 20 Tuft Density: 9 9 9 Dyn Load: 5 5 5 Stat Load: 4 4 5 Soiling Prop: 16 14 14 Abrasion Res: 10 10 10 Sub Total: 78 78 81 19 Panel Assess: 14 14 Total: 92 92 100 Calc Residential Grade: REHD2 6\* Calc Contract Grade: CHD 3\*

### **Test Results:**

Pile Mass g/m² (oz/yd²): 915 (27.0)SPM g/m² (oz/yd²): 597 (17.6)Stated Pile Height (mm): 3.1 Minimum Pile Height (mm): 0.0 Maximum Pile Height (mm): 0.0 Dynamic Loading Loss (%): 15.0 Static Loading Loss (%): 20.0 Tex (g/1000m): 469 Measured Pile Thickness (mm): 4.0 39.4 Machine Gauge (Tufts/dm): Meas Tufts Perp to Selvedge: 39.9 Meas Tufts Para to Selvedge: 48.0 Treated For Soiling Resistance: Yes Soil Resist Inhibitor: Yes Stain Resist Inhibitor: Yes

Label No:

14151

# Quality Assurance Test:

Cut Pile (%): 0 Loop Pile (%): 100 Panel Assessment Contract: 14 Panel Assessment Residential: 14 Suitable For Stairs: Yes Tile: Yes SheetGoods: No Fibre Signature: NBA:100

### **Calculations**

 Pile Height(mm):
 3.4

 Tuft Density(per dm²):
 1915.2

 GSPM(g/m²):
 415.0

 GSPM (abrasive) (g/m²):
 275.0

 Soiling Propensity:
 12.0
 +2.0

# **OAF Values**

OAF: 4.2

Calc Density (+-5%):0.14 0.149 0.16

Base Fibre: NYLON

Benchmarks:

RHD1 0 RHD2 3.5 REHD1 3.5 REHD2 3.5

# **Environmental Classification:**

ECS:

**TVOC** 

Level: 0

Calc B/M P/F
Acoustic: 4 3 PASS
Thermal: 26.8 15 PASS
VOC:

10

### Notes:

23/7/14 Submitted by T Nguyen. 30/7/14 Panel awarded CEHD(S) 4\*. 24/3/15 Deactivated and name CONSEQUENCE 2.0 - SEQUEL removed. 9/5/16 Now under Milliken. 14/9/16 Reactivated as inactivated by Licensee in error.